ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Notification dated 28th—31st July 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 28th August 1933, for constructing an additional shed for holding carpentry and weaving classes attached to the Government School at Anekal. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division, Bangalore, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. They should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred only as earnest money and be superscribed "tender for constructing an additional shed for holding carpentry and weaving classes attached to the Government School at Anekal, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on acccount of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for, and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer, Bangalore Division, will be final and legally binding.

12. Quotations must be shown in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimate rate will not be accepted.

13. Any tender containing a conditional clause contrary to these requirements or making stipulations not provided for either in this advertisement or the abstract quantity, will summarily be rejected.

Abstract estimate of quantities for constructing an additional shed attached to Government Middle School at Anekal (for holding carpentry and weaving classes).

Sl. No.	Items of work	Per	Quantity	Rate	Rate in words
1	Earth work excavation gravelly soil for foundation and filling in basement with watering and tamping.	C.yd.	31		
2	Filling in foundation with burnt stone jelly concrete in chunam mortar.	C.ft.	144		
3	Size stone in clay foundation and basement with burnt stones 6" apart.	"	913		
4	Superstructure, burnt brick in clay	"	1,180		
5	Burnt brick in chunam mortar	"	152		
6	Burnt stone slabs 5" to 6" thick roughly dressed and fixed in chunam.	S.ft.	218		
7	Teak wood doors with 1" battered shutters iron fittings including iron clamps painting (slate colour), etc., complete as per design.	"	56		
8	Teak wood windows with ½ panelled and ½ glazed shutters and frame with iron bars, painting (slate colour), etc., complete with	"	148½		

Sl. No.	Items of work	Per	Quantity	Rate	Rate in words
9	Teak wood wrought and put up, etc., complete with wood oiling.	C.ft.	140·20		
10	Providing burnt stone slabs pillars of 1′ wide 6″ thick and 9½′ height with dressing, cutting groove at top to receive bressemer, etc., complete, including fixing.	Each	6		
11	Plastering with chunam mortar, two coats ...	Sqr.	26·20		
12	Roofing with first class Mangalore tiles on teak reepers, etc., complete with wood oiling to reepers, etc.	,,	14·54		
13	Ridge tiles set in mortar	R.ft.	41½		
14	Chunam borders over roof	,,	7]		
15	Flooring with Cuddapah slabs of 1½″ thick over 3″ concrete and cement pointing, etc., complete.	Sqr.	8·30		
16	White washing 2 coats	,,	26·20		
17	Expanded metal 3″ mesh with teak frames of 2″×2″ including fixing and painting, etc., complete (slate colour).	S.ft.	413		
18	Cement pointing to Basement	Sqr.	1·90		
19	Teak wood Eave board 1″ x 9″ wide ordinary including (slate colour) painting two coats, etc., complete.	R.ft.	146		

M. A. SRINIVASACHARI,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification, dated 20th July 1933.

The attention of the public is invited to the detailed notification of 20th July 1933, regarding the sale of an old Public Works Department Sub-Division Office Building at Hunsur, published on page 923 of Part VI of the *Mysore Gazette*, dated 27th July 1933.

K. NARAYANA IYENGAR,
Executive Engineer.

KOLAR DIVISION.

Notification, dated 31st July—1st August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., 28th August 1933, for the work of opening a feeder channel to the Minakankurki Tank Reg. No. 88 of Goribidnur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th June 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of two hundred and eighty-five only in cash or Government Currency as earnest money, and be superscribed "Tender for the work of opening a feeder channel to Minakankurki Tank, Regd. No. 88 of Goribidnur Taluk," in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.